"MOORE HAVEN S/D"

<u>PARENT PARCEL</u> - 14-3S-16-02117-003 (DELETED - S/D takes up the entire parcel)

(Owner: Subrandy Limited Partnership)


(President: Lenvil H. Dicks)

HEADER PARCEL - 14-3S-16-02117-200

A S/D of a part of E1/2 of Sec. 14-3s-16E, as lies N. & E. of Moore Rd., consisting of 79.46 ac. & recorded in Plat Bk. 6, Pg. 198.

LOT # P.	ARCEL#
1	14-3s-16-02117-201
2	14-3s-16-02117-202
3	14-3s-16-02117-203
4	14-3s-16-02117-204
5	14-3s-16-02117-205
6	14-3s-16-02117-206
7	14-3s-16-02117-207
8	14-3s-16-02117-208
9	14-3s-16-02117-209
10	14-3s-16-02117-210
11	14-3s-16-02117-211
12	14-3s-16-02117-212
13	14-3s-16-02117-213
14	14-3s-16-02117-214
	1 2 3 4 5 6 7 8 9 10 11 12 13

Tax Dist.		003
Zoned	00	
Road		07
Topo		02
Utilities		03
NBHD Code	e 01431	6.04
ORB		819-553
Map #	68	
Value		\$ 20,000 / per lot



A PART OF THE E 1/2 OF SECTION 14, TOWNSHIP 3 SOUTH, RANGE 16 EAST,

MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGIN AT THE NE CORNER OF THE SE 1/4 OF THE NE 1/4 OF SAID SECTION 14 AND RUN S.01'30'08"E.

ALONG THE EAST LINE OF SAID SECTION 14, 2486.48 FEET TO THE NORTH RIGHT-OF-WAY OF MOORE ROAD; THENCE S.89'06'32"W. ALONG SAID NORTH RIGHT-OF-WAY, 347.16 FEET TO THE POINT OF CURVE OF A CURVE TO THE

30'40'24": THENCE NORTHWESTERLY ALONG THE ARC OF SAID CURVE FOR AN ARC DISTANCE OF 221.65 FEET TO THE POINT OF COMPOUND CURVE TO THE

AC DISTANCE OF 280.79 FEET: THENCE S.8750'03"W. STILL ALONG SAID

ARC DISTANCE OF 280.79 FEET: THENCE S.8750'03"W. STILL ALONG SAID

RICHT HAVING A RADIUS OF 693.49 FEET AND AN INCLUDED ANGLE OF

123'32'54"; THENCE NORTHWESTERLY ALONG THE ARC OF SAID CURVE FOR AN

ARC DISTANCE OF 280.79 FEET: THENCE S.8750'03"W. STILL ALONG SAID

RIGHT-OF-WAY, 375.56 FEET. THENCE N.01'54'15'W., 1233.16 FEET TO THE NORTH LINE OF THE SW 1/4 OF THE NE 1/4; THENCE N.89"22'21"E. ALONG SAID NORTH LINE, 513.72 FEET TO THE NW CORNER OF THE SE 1/4 OF THE

NE 1/4 OF SAID SECTION 14: THENCE N.89'26'30"E. ALONG THE NORTH LINE OF SAID SE 1/4 OF NE 1/4, 1303.93 FEET TO THE POINT OF BEGINNING.

COLUMBIA COUNTY, FLORIDA. CONTAINING 79.46 ACRES, MORE OR LESS.

RIGHT HAVING A RADIUS OF 414.02 FEET AND A CENTRAL ANGLE OF

RIGHT HAVING A RADIUS OF 693.49 FEET AND AN INCLUDED ANGLE OF

MOORE HAVEN" A SUBDIVISION IN:

SECTION 14, TOWNSHIP 3 SOUTH, RANGE 16 EAST, COLUMBIA COUNTY, FLORIDA.

KNOW ALL MEN BY THESE PRESENT THAT SUBRANDY LIMITED PARTNERSHIP WITH BRADLEY N. DICKS, AS GENERAL PARTNER HAS CAUSED THE LANDS HEREON DESCRIBED, TO BE SURVEYED, SUBDIVIDED AND PLATTED, TO BE KNOWN AS "MOORE HAVEN", AND THAT ALL ROADS STREETS AND ALL EASEMENTS FOR UTILITIES, DRAINAGE AND OTHER PURPOSES INDICATED THERETO AS SHOWN AND/OR DEPICTED HEREON ARE HEREBY DEDICATED TO THE PERPETUAL USE OF THE

ATTEST

AS GENERAL PARTNER

ACKNOWLEDGEMENT: STATE OF FLORIDA, COUNTY OF COLUMBIA.

I HEREBY CERTIFY THAT ON THIS 25th DAY OF March, 1998 A.D., BEFORE ME PERSONALLY APPEARED SUBRANDY LIMITED PARTNERSHIP WITH BRADLEY N. DICKS AS GENERAL PARTNER TO ME KNOWN TO BE THE PERSON DESCRIBED IN AND WHO EXECUTED THE FORGOING DEDICATION AND ACKNOWLEDGED THE EXECUTION THEREOF TO BE HIS FREE ACT AND DEED FOR THE USES AND PURPOSES THEREIN EXPRESSED. IN WITNESS WHEREOF I HAVE SET MY HAND AND SEAL ON THE ABOVE DATE.

NOTARY PUBLIC, STATE OF FLORIDA AT LARGE

MY COMMISSION EXPIRES:

OFFICIAL NOTARY SEAL EVA E TIMMONS IOTARY PUBLIC STATE OF FLORIDA MY COMMISSION EXP. AUG. 2,2001

COUNTY ATTORNEY CERTIFICATE:

I HEREBY CERTIFY THAT I HAVE EXAMINED THE FORGOING PLAT AND THAT IT COMPLIES IN FORM WITH THE COLUMBIA COUNTY SUBDIVISION ORDINANCE AND CHAPTER 177 OF THE FLORIDA STATUTES.

THIS PLAT IS HEREBY APPROVED BY THE COLUMBIA COUNTY COMMISSION THIS DAY OF 4/16/88 . 1998, A.D.

I HEREBY CERTIFY THAT THE IMPROVEMENTS HAVE BEEN CONSTRUCTED IN AN ACCEPTABLE MANNER AND IN ACCORDANCE WITH COUNTY SPECIFICATIONS OR THAT A PERFORMANCE BOND OR INSTRUMENT IN THE AMOUNT OF \$

HAS BEEN POSTED TO ASSURE COMPLETION OF ALL REQUIRED IMPROVEMENTS AND

THIS PLAT HAVING BEEN APPROVED BY THE COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS IS ACCEPTED FOR FILES AND RECORDED THIS 22 198-199 DAY OF COUNTY 1998, A.D. IN PLAT BOOK, G., PAGE 198-199

APPROVAL: STATE OF FLORIDA, COUNTY OF COLUMBIA.

PUBLIC WORKS DIRECTOR, COLUMBIA COUNTY, FLORIDA.

MAINTENANCE IN CASE OF DEFAULT.

CERTIFICATE OF CLERK:

SURVEYOR'S NOTES:

BOUNDARY BASED ON MONUMENTATION FOUND IN ACCORDANCE WITH THE RETRACEMENT OF

THE ORIGINAL SURVEY FOR THE DEED OF RECORD AS PROVIDED BY CLIENT.

BEARINGS ARE BASED ON AN ASSUMED BEARING OF N.01'30'48"W. FOR THE EAST LINE THEREOF. SOME PORTIONS OF THIS PARCEL ARE IN ZONE "A" AND MAY BE SUBJECT TO FLOODING HOWEVER, NO BASE FLOOD ELEVATION HAS BEEN DETERMINED FOR ZONE "A". SOME PORTIONS OF THIS PARCEL ARE IN ZONE "X" AND ARE DETERMINED TO BE CUTSIDE THE 500 YEAR FLOOD PLAIN AS PER FLOOD INSURANCE RATE MAP, DATED 6 JAN. 1988 COMMUNITY PANEL NO. 120070 0125 B. HOWEVER, THE FLOOD INSURANCE RATE MAPS ARE SUBJECT TO CHANGE.

4. IF THEY EXIST, NO UNDERGROUND ENCROACHMENTS AND/OR UTILITIES WERE LOCATED FOR THIS SURVEY EXCEPT AS SHOWN HEREON.

5. THIS SURVEY WAS COMPLETED WITHOUT THE BENEFIT OF A TITLE COMMITMENT OR A TITLE

6. EASEMENTS OF (20") TWENTY FEET IN WIDTH ALONG THE ROAD FRONT OF EACH LOT AND (7.5") SEVEN AND ONE-HALF FEET IN WIDTH ALONG EACH SIDE LOT LINES ARE HEREBY CREATED AND PROVIDED FOR THE PURPOSE OF ACCOMMODATING OVERHEAD, SURFACE, AND UNDERGROUND UTILITIES AND DRAINAGE. WHERE AN AREA GREATER THAN ONE LOT IS USED AS A BUILDING SITE, ONLY THE OUTSIDE BOUNDARY OF SAID SITE SHALL BE SUBJECT TO THE LOT LINE EASEMENT.

THERE MAY BE ADDITIONAL RESTRICTIONS THAT ARE NOT RECORDED ON THIS PLAT THAT MAY


BE FOUND IN THE PUBLIC RECORDS OF COLUMBIA COUNTY. 8. PRELIMINARY APPROVAL DATE: OCTOBER 2, 1997.

9. SURVEY CLOSURE PRECISION EXCEEDS THE REQUIREMENTS OF THE MINIMUM TECHNICAL STANDARDS

FOR SURVEYING IN THE STATE OF FLORIDA

THE EASEMENTS REFERRED TO HEREON IN NOTE # 6 SHALL CONSTITUTE EASEMENTS FOR THE CONSTRUCTION, INSTALLATION, MAINTENANCE AND OPERATION OF ELECTRICITY, TELEPHONE, CABLE TELEVISION, AND PUBLIC UTILITIES WHICH MAY SERVICE THE LANDS ENCOMPASSED BY THIS PLAT.

SECTION 14, TOWNSHIP 3 SOUTH, RANGE 16 EAST.



LOCATION SKETCH NOT TO SCALE

ENGINEER'S CERTIFICATION:

THE UNDERSIGNED REGISTERED PROFESSIONAL ENGINEER, HEREBY CERTIFY THAT THE PROPOSED DRAMAGE SYSTEM IS SUFFICIENT WITH RESPECT TO THE REQUIREMENTS OF THAT ORDINANCE

DESCRIPTION:

DALE C. JOHNS
PROFESSIONAL ENGINEER # 45263 33 HIGHLANDS COURT LAKE CITY, FLORIDA 32055

SURVEYOR'S CERTIFICATION:

I HEREBY CERTIFY THAT THIS SURVEY WAS MADE UNDER MY RESPONSIBLE CHARGE AND MEETS THE MINIMON TO TECHNICAL STANDARDS AS SET FORTH BY THE FLORIDA BOARD OF PROFESSIONAL SURVEYORS AND MAPPERS IN CHAPTER 61G17-6, FLORIDA ADMINISTRATIVE CODE, PURSUANT TO SECTION 478.017, FLORIDA STATUTES.

1-5-98

FLORIDA CERTIFICATION #1079

NOTE: UNLESS IT BEARS THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER THIS DRAWING, SKETCH, PLAT OR MAP IS FOR INFORMATIONAL PURPOSES ONLY AND IS NOT VALID.



LAND SURVEYORS AND MAPPERS

1426 WEST DUVAL STREET LAKE CITY, FLORIDA 32055

TELEPHONE: (904) 752-7163 FAX: (904) 752-5573 WORK ORDER # L-7388

127 86